



- NOTES:**
1. THE CONTRACTOR SHALL FIELD VERIFY THE HORIZONTAL AND VERTICAL LOCATIONS OF ALL EXISTING PUBLIC AND PRIVATE UTILITIES THAT HAVE OR MAY HAVE ANY EFFECT ON THE PROPOSED IMPROVEMENTS BEFORE ANY WORK COMMENCES. IF ANY DISCREPANCY FROM THE PLANS IS FOUND, THE CONTRACTOR IS TO NOTIFY THE CITY OR ITS REPRESENTATIVE BEFORE PROCEEDING FURTHER.
 2. THE EXISTING SANITARY SERVICE LINE AS SHOWN IN PROFILE REFLECTS THE FLOWLINE AT THE MANHOLE. THE SERVICE LINES ARE ANTICIPATED TO CROSS ABOVE THE PROPOSED STORM SEWER LINE WITH 12-IN. OF MINIMUM CLEARANCE. CONTRACTOR TO PROTECT THE SERVICE LINES DURING INSTALLATION. IF MINIMUM CLEARANCES CANNOT BE MAINTAINED, CONTRACTOR TO REPLACE THE SECTION OF SERVICE LINE OR INSTALL CONFLICT MANHOLE, AS DIRECTED BY THE CITY OR ITS REPRESENTATIVE.

BENCHMARK NOTE:
 CITY OF HUNTSVILLE MON.#6023
 MONUMENT IS A 2-1/2" ALUMINUM CAP IN CONCRETE
 MONUMENT. MARK IS LOCATED IN ISLAND AT THE
 INTERSECTION OF HWY 45 AND VETERANS MEMORIAL PKWY.
 NORTHING: 10,260,078.59
 EASTING: 3,790,372.05
 ELEV. 404.28' (NAVD 88)

TBM#17
 CUT "X" IN CONCRETE
 NORTHING: 10,256,596.23
 EASTING: 3,796,747.24
 ELEVATION: 406.44'

TBM SH
 CUT "X" IN CONCRETE
 NORTHING: 10,256,563.23
 EASTING: 3,796,235.06
 ELEVATION: 382.86'

ADDENDUM No. 1



TO ARRANGE FOR LINES TO BE TURNED OFF OR REMOVED,
 CALL CENTERPOINT AT 713-207-2222
NOTICE:
 For your safety, you are required by Texas law to call 811 at least
 48 hours before you dig so that underground lines can be marked.
 This verification does not fulfill your obligation to call 811.

VERIFICATION OF PRIVATE UTILITIES

Mike Browne DATE 01-25-23
 CenterPoint Energy/Natural Gas Facilities Verifications ONLY
 (This Signature verifies existing underground facilities - not to be used for conflict verification)
 Signature Valid for six months

Mike Browne DATE 01-25-23
 CenterPoint Energy/UNDERGROUND Electrical Facilities Verifications ONLY
 (This Signature verifies existing underground facilities - not to be used for conflict verification)
 Signature Valid for six months

NO SIGNATURE REQUIRED BY FACILITY OWNER DATE N/A
 Entergy/Electrical Facilities Verifications
 (This Signature verifies existing underground facilities - not to be used for conflict verification)
 Signature Valid for one year

Debra Ruppel DATE 01/23/23
 AT&T Texas / SWBT Facilities
 (Approved for AT&T Texas / SWBT UNDERGROUND Conduit Facilities only)
 Signature Valid for one year



ADDENDUM No. 1 - ADDED	P.R.	J.C.F.	J.C.F.	3/29/23
Revision	By	Chk.	Appr.	Date

**CITY OF HUNTSVILLE
 17TH STREET STORM SEWER
 IMPROVEMENTS**

**17TH STREET
 PLAN & PROFILE
 BEGINNING TO END (BL "A")**

LJA Engineering, Inc.
 11821 East Freeway Phone 713.450.1300
 Suite 360 Fax 713.450.1385
 Houston, Texas 77029 FRN - F-1386

DESIGN: J.C.F. JOB No. E243-0020 Cont. No.
 DRAWN: P.R. DATE: FEBRUARY 2023
 CHECKED: SCALE: 1"=20' HORIZ.; 1"=4' VER.
 APPROVED: SHEET No. 04 Of 12