



City of Huntsville  
1220 11<sup>th</sup> Street  
Huntsville, TX 77320  
Lucy Gonzalez  
Procurement Manager  
Telephone: (936) 291-5495  
Email: [purchasing@huntsvilletx.gov](mailto:purchasing@huntsvilletx.gov)

## ADDENDUM #2

Title	Bid Number	Closing Date	Issued Date
Bid NO. 25-25 Steet Asphaltic Concrete Paving with Milling Services and Street Reconstruction Services	25-25	April 22, 2025, at 2:00 P.M. Central Standard Time	April 15, 2025

### TO ALL PROSPECTIVE BIDDERS:

The information contained in this Addendum supersedes information contained in the Contract Documents to the extent indicated. All information contained in the Contract Documents remain in full force and effect unless specifically modified herein. All Respondents shall acknowledge the receipt of the Addendum in the space provided on this Addendum Form and submit this form with your bid packet. Failure to do so will result in Respondent disqualification.

The attention of all prospective Respondents is directed to the following modifications for the above referenced project.

### Questions and Answers

**Question No. 1:** On the PCC streets for 17<sup>th</sup> street, it says these concrete streets are to go back with 2" asphalt. It just shows to lime stabilize these and place 2" back, are we needing to place a 6"-8" base course in this? it does not show. But I understand the ACC but I'm not seeing a Base material to be included on the PCC. We can either bid it as a Limestone or can bid it as a Black Base.

**Answer:** You may bid the PCC street with either 4" inches limestone or black base then 2" tyD HMA surface mix to fill from stabilized subgrade to gutter.

**Question No. 2:** 17th street reconstruction removing existing concrete 4- 6 inch road and gutter and replacing with stabilized subgrade and 2 inch HMA surface will result in a lowered road surface. Note under Reconstruction description states *Reconstruction on streets with curb and gutter drainage shall require replacement of the existing Curb and gutter and driveways.* The existing conditions along this road have substantial parking areas, sidewalks and inlets That would be impacted by the lowered road and Curb and Gutter. It appears all would need to be removed and reconstructed as well.

**To clarify, are all these expected to be adjusted?**

**Answer:** The finish grade of the reconstructed street shall be the same elevation as the existing street was. C&G, pavement, and driveway approaches shall be replaced. Sidewalks not to be replaced on this contract. Additional limestone or black base will be needed to make up the difference in existing and new pavement thickness.

**Question No. 3:**  
**Answer:**

**Question No. 4:**  
**Answer:**

**Please include signed copy of Addendum with submitted Solicitation Packet.**

**Responder Name:** \_\_\_\_\_

**Address:** \_\_\_\_\_

**Telephone Number:** \_\_\_\_\_

\_\_\_\_\_

**Printed Name of Contact**

**Fax Number:** \_\_\_\_\_

**Email Address:** \_\_\_\_\_

\_\_\_\_\_

**Authorized Signature**