



Description	Quantity	A-1		Grisham	
		Construction	Willis, TX	Construction	Huntsville, TX
		Unit Price	Extension	Unit Price	Extension
Furnish all materials, labor equipment and install mobilization to include traffic control, minor cleaning & grubbing, seeding, fertilizer, saw cutting existing asphalt, and general cleanup	1	\$ 10,507.00	\$ 10,507.00	\$ 7,500.00	\$ 7,500.00
Furnish all materials, labor equipment and install Erosion Control silt fence @ specified locations on plan prior to construction.	250	\$ 3.38	\$ 845.00	\$ 3.95	\$ 987.50
Furnish all materials, labor equipment and install earthwork manipulation cut (425cy) and fill (160cy) including existing pavement.	1	\$ 6,994.00	\$ 6,994.00	\$ 6,920.00	\$ 6,920.00
Furnish all materials, labor equipment and install 8" limestone flexible base and compacted 95%.	745	\$ 17.30	\$ 12,888.50	\$ 15.00	\$ 11,175.00
Furnish all materials, labor equipment and install 2" Type D HMAc and all oil/fact appurtenances.	72	\$ 118.92	\$ 8,562.24	\$ 117.34	\$ 8,448.48
Furnish all materials, labor equipment and install 4" Type B HMAc and all oil/fact appurtenances.	144	\$ 78.26	\$ 11,269.44	\$ 117.34	\$ 16,896.96
Furnish all materials, labor equipment and install 6" concrete flume with #4 rebar 12" oc. Both ways and all expansion/contraction joint material and appurtenances.	50	\$ 22.74	\$ 1,137.00	\$ 5.20	\$ 260.00
Furnish all materials, labor equipment and install STD 24" concrete curb & gutter per COH specifications and all expansion/contraction joint material and appurtenances.	225	\$ 18.10	\$ 4,072.50	\$ 21.34	\$ 4,801.50
Total Amount			\$ 56,275.68		\$ 56,989.44

Bid maybe awarded in whole or by parts

*NOTICE: Bid award is contingent upon vendor meeting bid requirements and formal authorization by City officials

Billie Smith (Purchasing Manager)